

EMC TEST Report

Issued Date : Jun. 30, 2006

Report No. : 0605019

Equipment : 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card

Model No. : DGE-528T

Applicant : D-Link Corp.

Address : 4F, No. 289, Sinhu 3rd Rd., Neihu District, Taipei
City 114, Taiwan R.O.C.


Tested by:

Neutron Engineering Inc. EMC Laboratory


Data of Test:

May 04, 2006 ~ Jun. 29, 2006

Testing Engineer :


(Josh Li)

Technical Manager :


(Jeff Yang)

Authorized Signatory :


(Andy Chiu)

NEUTRON ENGINEERING INC.

No. 132-1, Lane 329, Sec. 2, Palain Rd.,
Shijr City, Taipei, Taiwan
TEL : (02) 2646-5426 FAX : (02) 2646-6815



Declaration

Neutron represents to the client that testing is done in accordance with standard procedures as applicable and that test instruments used has been calibrated with the standards traceable to National Measurement Laboratory (NML) of R.O.C., or National Institute of Standards and Technology (NIST) of U.S.A.

Neutron's reports apply only to the specific samples tested under conditions. It is manufacture's responsibility to ensure that additional production units of this model are manufactured with the identical electrical and mechanical components. **Neutron** shall have no liability for any declarations, inferences or generalizations drawn by the client or others from **Neutron** issued reports.

Neutron's reports must not be used by the client to claim product endorsement by the authorities or any agency of the Government.

This report is the confidential property of the client. As a mutual protection to the clients, the public and **Neutron-self**, extracts from the test report shall not be reproduced except in full with **Neutron's** authorized written approval.

Neutron's laboratory quality assurance procedures are in compliance with the **ISO Guide 17025** requirements, and accredited by the conformity assessment authorities listed in this test report.

Limitation

For the use of the authority's logo is limited unless the Test Standard(s)/Scope(s)/Item(s) mentioned in this test report is (are) included in the conformity assessment authorities acceptance respective.

| Table of Contents | Page |
|---|-------------|
| 1 . CERTIFICATION | 6 |
| 2 . SUMMARY OF TEST RESULTS | 7 |
| 2.1 TEST FACILITY | 8 |
| 2.2 MEASUREMENT UNCERTAINTY | 8 |
| 3 . GENERAL INFORMATION | 9 |
| 3.1 GENERAL DESCRIPTION OF EUT | 9 |
| 3.2 DESCRIPTION OF TEST MODES | 10 |
| 3.3 BLOCK DIGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED | 10 |
| 3.4 DESCRIPTION OF SUPPORT UNITS | 10 |
| 4 . EMC EMISSION TEST | 10 |
| 4.1 CONDUCTED EMISSION MEASUREMENT | 10 |
| 4.1.1 POWER LINE CONDUCTED EMISSION | 10 |
| 4.1.2 MEASUREMENT INSTRUMENTS LIST | 10 |
| 4.1.3 TEST PROCEDURE | 10 |
| 4.1.4 DEVIATION FROM TEST STANDARD | 10 |
| 4.1.5 TEST SETUP | 10 |
| 4.1.6 EUT OPERATING CONDITIONS | 10 |
| 4.1.7 TEST RESULTS | 10 |
| 4.2 RADIATED EMISSION MEASUREMENT | 10 |
| 4.2.1 LIMITS OF RADIATED EMISSION MEASUREMENT | 10 |
| 4.2.2 MEASUREMENT INSTRUMENTS LIST | 10 |
| 4.2.3 TEST PROCEDURE | 10 |
| 4.2.4 DEVIATION FROM TEST STANDARD | 10 |
| 4.2.5 TEST SETUP | 10 |
| 4.2.6 EUT OPERATING CONDITIONS | 10 |
| 4.2.7 TEST RESULTS | 10 |
| 5 . EMC IMMUNITY TEST | 10 |
| 5.1 STANDARD COMPLIANCE/SERVIRITY LEVEL/CRITERIA | 10 |
| 5.2 GENERAL PERFORMANCE CRITERIA | 10 |
| 5.3 GENERAL PERFORMANCE CRITERIA TEST SETUP | 10 |
| 5.4 ESD TESTING | 10 |
| 5.4.1 TEST SPECIFICATION | 10 |
| 5.4.2 MEASUREMENT INSTRUMENTS | 10 |
| 5.4.3 TEST PROCEDURE | 10 |
| 5.4.4 DEVIATION FROM TEST STANDARD | 10 |

| Table of Contents | Page |
|---|-------------|
| 5.4.5 TEST SETUP | 10 |
| 5.4.6 TEST RESULTS | 10 |
| 5.4.7 PHOTO(S) SHOWN THE LOCATION(S) OF ESD EVALUATED | 10 |
| 5.5 RS TESTING | 10 |
| 5.5.1 TEST SPECIFICATION | 10 |
| 5.5.2 MEASUREMENT INSTRUMENTS | 10 |
| 5.5.3 TEST PROCEDURE | 10 |
| 5.5.4 DEVIATION FROM TEST STANDARD | 10 |
| 5.5.5 TEST SETUP | 10 |
| 5.5.6 TEST RESULTS | 10 |
| 5.6 EFT/BURST TESTING | 10 |
| 5.6.1 TEST SPECIFICATION | 10 |
| 5.6.2 MEASUREMENT INSTRUMENTS | 10 |
| 5.6.3 TEST PROCEDURE | 10 |
| 5.6.4 DEVIATION FROM TEST STANDARD | 10 |
| 5.6.5 TEST SETUP | 10 |
| 5.6.6 TEST RESULTS | 10 |
| 5.7 SURGE TESTING | 10 |
| 5.7.1 TEST SPECIFICATION | 10 |
| 5.7.2 MEASUREMENT INSTRUMENTS | 10 |
| 5.7.3 TEST PROCEDURE | 10 |
| 5.7.4 DEVIATION FROM TEST STANDARD | 10 |
| 5.7.5 TEST SETUP | 10 |
| 5.7.6 TEST RESULTS | 10 |
| 5.8 INJECTION CURRENT TESTING | 10 |
| 5.8.1 TEST SPECIFICATION | 10 |
| 5.8.2 MEASUREMENT INSTRUMENTS | 10 |
| 5.8.3 TEST PROCEDURE | 10 |
| 5.8.4 DEVIATION FROM TEST STANDARD | 10 |
| 5.8.5 TEST SETUP | 10 |
| 5.8.6 TEST RESULTS | 10 |
| 5.9 POWER FREQUENCY MAGNETIC FIELD TESTING | 10 |
| 5.9.1 TEST SPECIFICATION | 10 |
| 5.9.2 MEASUREMENT INSTRUMENTS | 10 |
| 5.9.3 TEST PROCEDURE | 10 |
| 5.9.4 DEVIATION FROM TEST STANDARD | 10 |
| 5.9.5 TEST SETUP | 10 |
| 5.9.6 TEST RESULTS | 10 |
| 5.10 VOLTAGE INTERRUPTION/DIPS TESTING | 10 |
| 5.10.1 TEST SPECIFICATION | 10 |
| 5.10.2 MEASUREMENT INSTRUMENTS | 10 |

| Table of Contents | Page |
|-------------------------------------|-------------|
| 5.10.3 TEST PROCEDURE | 10 |
| 5.10.4 DEVIATION FROM TEST STANDARD | 10 |
| 5.10.5 TEST SETUP | 10 |
| 5.10.6 TEST RESULTS | 10 |
| 6 . EUT TEST PHOTO | 10 |

1. CERTIFICATION

Equipment : 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card
Trade Name : D-LINK
Model No. : DGE-528T
Applicant : D-Link Corp.
Data of Test : May 04, 2006 ~ Jun. 29, 2006
Test Item : ENGINEERING SAMPLE
Standards : EN 55022:1998+A1: 2000+A2: 2003 Class B
 EN 55024:1998+A1: 2001+A2: 2003
 IEC 61000-4-2: 2001
 IEC 61000-4-3: 2002
 IEC 61000-4-4: 1995+A1: 2000+A2: 2001
 IEC 61000-4-5: 2001
 IEC 61000-4-6: 2001
 IEC 61000-4-8: 2001
 IEC 61000-4-11: 2001

The above equipment has been tested and found compliance with the requirement of the relative standards by Neutron Engineering Inc. EMC Laboratory.

The test data, data evaluation, and equipment configuration contained in our test report (Ref No. NEI-EMC-1-0605019) were obtained utilizing the test procedures, test instruments, test sites that has been accredited by the Authority of NVLAP and CNLA according to the ISO-17025 quality assessment standard and technical standard(s).

2. SUMMARY OF TEST RESULTS

Test procedures according to the technical standards:

| EMC Emission | | | | |
|---|--------------------------------|-----------------------|----------|--------|
| Standard | Test Item | Limit | Judgment | Remark |
| EN 55022:1998 +A1: 2000+A2: 2003 | Conducted Emission | Class B | PASS | |
| | Radiated Emission | Class B | PASS | |
| EN 61000-3-2:2000 | Harmonic Current Emission | Class A | N/A | |
| EN 61000-3-3:1995 +A1: 2001 | Voltage Fluctuations & Flicker | ----- | N/A | |
| EMC Immunity (EN 55024:1998+A1: 2001+A2: 2003) | | | | |
| Section | Test Item | Performance Criteria | Judgment | Remark |
| IEC 61000-4-2:2001 | Electrostatic Discharge | B | PASS | |
| IEC 61000-4-3:2002 | RF electromagnetic field | A | PASS | |
| IEC 61000-4-4:1995 +A1: 2000+A2: 2001 | Fast transients | B | PASS | |
| IEC 61000-4-5:2001 | Surges | B | PASS | |
| IEC 61000-4-6:2001 | Injected Current | A | PASS | |
| IEC 61000-4-8:2001 | Power Frequency Magnetic Field | A | PASS | |
| IEC 61000-4-11:2001 | Volt. Interruptions Volt. Dips | B / C / C NOTE (3) | PASS | |

NOTE:

- (1) "N/A" denotes test is not applicable in this Test Report
- (2) The power consumption of EUT is less than 75W and no Limits apply.
- (3) Voltage dip: >95% reduction – Performance Criteria **B**
Voltage dip: 30% reduction – Performance Criteria **C**
Voltage Interruption: >95% reduction – Performance Criteria **C**
- (4) For client's request and manual description, the test will not be executed.

2.1 TEST FACILITY

The test facilities used to collect the test data in this report is **C01/OS02** at the location of No.132-1, Lane 329, Sec. 2, Palain Road, Shijr City, Taipei, Taiwan.

2.2 MEASUREMENT UNCERTAINTY

The reported uncertainty of measurement $y \pm U$, where expended uncertainty **U** is based on a standard uncertainty multiplied by a coverage factor of **k=2**, providing a level of confidence of approximately **95 %**.

A. Conducted Measurement :

| Test Site | Method | Measurement Frequency Range | U , (dB) | NOTE |
|-----------|--------|-----------------------------|----------|------|
| C01 | ANSI | 150 KHz ~ 30MHz | 1.94 | |

B. Radiated Measurement :

| Test Site | Method | Measurement Frequency Range | Ant. H / V | U , (dB) | NOTE |
|-----------|--------|-----------------------------|------------|----------|------|
| OS-01 | ANSI | 30MHz ~ 200MHz | V | 3.82 | |
| | | 30MHz ~ 200MHz | H | 3.60 | |
| | | 200MHz ~ 1,000MHz | V | 3.86 | |
| | | 200MHz ~ 1,000MHz | H | 3.94 | |
| OS-02 | ANSI | 30MHz ~ 200MHz | V | 2.48 | |
| | | 30MHz ~ 200MHz | H | 2.16 | |
| | | 200MHz ~ 1,000MHz | V | 2.50 | |
| | | 200MHz ~ 1,000MHz | H | 2.66 | |

3. GENERAL INFORMATION

3.1 GENERAL DESCRIPTION OF EUT

| | |
|------------------------|--|
| Equipment | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card |
| Trade Name | D-LINK |
| Model No. | DGE-528T |
| OEM Brand/Model No. | N/A |
| Model Difference | N/A |
| Product Description | The EUT is a 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card. Based on the application, features, or specification exhibited in User's Manual, the EUT is considered as an ITE/Computing Device. More details of EUT technical specification, please refer to the User's Manual. |
| Power Source | Supplied from PC PCI Slot. |
| Power Rating | N/A |
| Connecting I/O Port(s) | Please refer to the User's Manual |
| Products Covered | N/A |

Note:

1. For a more detailed features description, please refer to the manufacturer's specifications or the User's Manual.

3.2 DESCRIPTION OF TEST MODES

To investigate the maximum EMI emission characteristics generated from EUT, the test system was pre-scanning tested based on the consideration of following EUT operation mode or test configuration mode which possibly have effect on EMI emission level. Each of these EUT operation mode(s) or test configuration mode(s) mentioned above was evaluated respectively.


| Pretest Test Mode | Description |
|-------------------|-------------|
| Mode 1 | 1G-1G |
| Mode 2 | 100M-100M |
| Mode 2 | 10M-10M |

| For Conducted Test | |
|--------------------|-------------|
| Final Test Mode | Description |
| Mode 1 | 1G-1G |
| Mode 2 | 100M-100M |
| Mode 2 | 10M-10M |

| For Radiated Test | |
|-------------------|-------------|
| Final Test Mode | Description |
| Mode 1 | 1G-1G |
| Mode 2 | 100M-100M |

| For EMS Test | |
|-----------------|-------------|
| Final Test Mode | Description |
| Mode 1 | 1G-1G |

3.3 BLOCK DIGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED



C-1 Video Cable
C-2 Data Cable
C-3 Data Cable
C-4 Interface Cable
C-5 Centronics Cable
C-6 RJ-45 Cable

3.1 DESCRIPTION OF SUPPORT UNITS

The EUT has been tested as an independent unit together with other necessary accessories or support units. The following support units or accessories were used to form a representative test configuration during the tests.

| Item | Equipment | Mfr/Brand | Model/Type No. | FCC ID | Series No. | Note |
|------|--|-----------|-----------------|--------|-----------------|------|
| E-1 | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | D-LINK | DGE-528T | DOC | N/A | EUT |
| E-2 | 19" LCD Monitor | Samsung | SyncMaster 193P | GH19PH | DI19H4JXC05517A | |
| E-3 | PC | IBM | 8175-I5V | DOC | 99MYG14 | |
| E-4 | Printer | SII | DPU-414 | DOC | 1045105A | |
| E-5 | Modem | ACEEX | DM-1414V | DOC | 8041708 | |
| E-6 | PS/2 K/B | Logitech | Y-SJ17(ACK260A) | DOC | SYU44664880 | |
| E-7 | PS/2 Mouse | Logitech | M-SBF69 | DOC | HCA44601156 | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

| Item | Shielded Type | Ferrite Core | Length | Note |
|------|---------------|--------------|--------|------|
| C-1 | YES | YES | 1.8M | |
| C-2 | YES | NO | 1.5M | |
| C-3 | YES | NO | 1.5M | |
| C-4 | YES | NO | 1.8M | |
| C-5 | YES | NO | 1.8M | |
| C-6 | NO | NO | 20M | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Note:

- (1) The support equipment was authorized by Declaration of Confirmation.
- (2) For detachable type I/O cable should be specified the length in cm in 『Length』 column.

4. EMC EMISSION TEST

4.1 CONDUCTED EMISSION MEASUREMENT

4.1.1 POWER LINE CONDUCTED EMISSION (Frequency Range 150KHz-30MHz)

| FREQUENCY (MHz) | Class A (dBuV) | | Class B (dBuV) | |
|-----------------|----------------|---------|----------------|-----------|
| | Quasi-peak | Average | Quasi-peak | Average |
| 0.15 -0.5 | 79.00 | 66.00 | 66 - 56 * | 56 - 46 * |
| 0.50 -5.0 | 73.00 | 60.00 | 56.00 | 46.00 |
| 5.0 -30.0 | 73.00 | 60.00 | 60.00 | 50.00 |

Note:

- (1) The tighter limit applies at the band edges.
- (2) The limit of " * " marked band means the limitation decreases linearly with the logarithm of the frequency in the range.

4.1.2 MEASUREMENT INSTRUMENTS LIST

| Item | Kind of Equipment | Manufacturer | Type No. | Serial No. | Calibrated until |
|------|-------------------|-----------------|------------|------------|------------------|
| 1 | LISN | Rolf Heine | NNB-2/16Z | 98053 | Dec. 19, 2006 |
| 2 | 4L-V-LISN | Rolf Heine | NNB-4/63TL | 02/10040 | Apr. 10, 2007 |
| 3 | ISN | SCHAFFNER | ISN T400 | 16017 | Mar. 31, 2007 |
| 4 | Pulse Limiter | Electro-Metrics | EM-7600 | 112644 | Nov. 29, 2006 |
| 5 | 50Ω Terminator | N/A | N/A | N/A | May.11, 2007 |
| 6 | Test Cable | N/A | C01 | N/A | Nov. 29, 2006 |
| 7 | EMI Test Receiver | R&S | ESCI | 100082 | Feb. 01, 2007 |

Remark: " N/A" denotes No Model No. , Serial No. or No Calibration specified.


4.1.3 TEST PROCEDURE

- a. The EUT was placed 0.4 meters from the horizontal ground plane with EUT being connected to the power mains through a line impedance stabilization network (LISN). All other support equipments powered from additional LISN(s). The LISN provide 50 Ohm/ 50uH of coupling impedance for the measuring instrument.
- b. Interconnecting cables that hang closer than 40 cm to the ground plane shall be folded back and forth in the center forming a bundle 30 to 40 cm long.
- c. I/O cables that are not connected to a peripheral shall be bundled in the center. The end of the cable may be terminated, if required, using the correct terminating impedance. The overall length shall not exceed 1 m.
- d. LISN at least 80 cm from nearest part of EUT chassis.
- e. For the actual test configuration, please refer to the related Item –EUT Test Photos.

4.1.4 DEVIATION FROM TEST STANDARD

No deviation

4.1.5 TEST SETUP



4.1.6 EUT OPERATING CONDITIONS

The EUT exercise program used during radiated and/or conducted emission measurement was designed to exercise the various system components in a manner similar to a typical use. The program contained on a PC hard disk and is auto-starting on power-up. Once loaded, the program sequentially exercises each system component in turn. The sequence used is:

1. Read (write) from (to) mass storage device (Disk).
2. Send "H" pattern to video port device (Monitor).
3. Send " H " pattern to parallel port device (Printer).
4. Send " H " pattern to serial port device (Modem).
5. Repeated from 2 to 4 continuously.

As the keyboard and mouse are strictly input devices, no data is transmitted to (from) them during test. They are, however, continuously scanned for data input activity.


4.1.7 TEST RESULTS

| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 22 °C | Relative Humidity : | 58 % |
| Pressure : | 1014 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 1G-1G | | |

| Freq. (MHz) | Terminal L/N | Measured(dBuV) | | Limits(dBuV) | | Margin (dB) | Note |
|----------------|-----------------|----------------|---------|--------------|---------|----------------|------|
| | | QP-Mode | AV-Mode | QP-Mode | AV-Mode | | |
| 0.38 | Line | 40.32 | * | 58.32 | 48.32 | -18.00 | (QP) |
| 2.53 | Line | 39.14 | * | 56.00 | 46.00 | -16.86 | (QP) |
| 4.14 | Line | 39.22 | * | 56.00 | 46.00 | -16.78 | (QP) |
| 4.76 | Line | 42.45 | * | 56.00 | 46.00 | -13.55 | (QP) |
| 6.79 | Line | 42.78 | * | 60.00 | 50.00 | -17.22 | (QP) |
| 19.68 | Line | 39.41 | * | 60.00 | 50.00 | -20.59 | (QP) |

Remark

- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz; SPA setting in RBW=10KHz,VBW =10KHz, Swp. Time = 0.3 sec./MHz. Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=1MHz,VBW=10Hz, Swp. Time =0.3 sec./MHz.
- (2) All readings are QP Mode value unless otherwise stated AVG in column of 'Note'. If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform. In this case, a "*" marked in AVG Mode column of Interference Voltage Measured.
- (3) Measuring frequency range from 150KHz to 30MHz.




| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 22 °C | Relative Humidity : | 58 % |
| Pressure : | 1014 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 100M-100M | | |

| Freq. (MHz) | Terminal L/N | Measured(dBuV) | | Limits(dBuV) | | Margin (dB) | Note |
|----------------|-----------------|----------------|---------|--------------|---------|----------------|------|
| | | QP-Mode | AV-Mode | QP-Mode | AV-Mode | | |
| 0.40 | Neutral | 41.52 | * | 57.92 | 47.92 | -16.40 | (QP) |
| 2.52 | Neutral | 38.74 | * | 56.00 | 46.00 | -17.26 | (QP) |
| 4.14 | Neutral | 41.02 | * | 56.00 | 46.00 | -14.98 | (QP) |
| 4.75 | Neutral | 40.25 | * | 56.00 | 46.00 | -15.75 | (QP) |
| 6.93 | Neutral | 43.39 | * | 60.00 | 50.00 | -16.61 | (QP) |
| 19.14 | Neutral | 40.01 | * | 60.00 | 50.00 | -19.99 | (QP) |

Remark

- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz; SPA setting in RBW=10KHz,VBW =10KHz, Swp. Time = 0.3 sec./MHz ◦ Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=1MHz,VBW=10Hz, Swp. Time =0.3 sec./MHz ◦
- (2) All readings are QP Mode value unless otherwise stated AVG in column of『Note』. If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform ◦ In this case, a “ * ” marked in AVG Mode column of Interference Voltage Measured ◦
- (3) Measuring frequency range from 150KHz to 30MHz ◦




| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 22 °C | Relative Humidity : | 58 % |
| Pressure : | 1014 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 100M-100M | | |

| Freq. (MHz) | Terminal L/N | Measured(dBuV) | | Limits(dBuV) | | Margin (dB) | Note |
|----------------|-----------------|----------------|---------|--------------|---------|----------------|------|
| | | QP-Mode | AV-Mode | QP-Mode | AV-Mode | | |
| 0.39 | Line | 41.13 | * | 58.04 | 48.04 | -16.91 | (QP) |
| 1.76 | Line | 35.50 | * | 56.00 | 46.00 | -20.50 | (QP) |
| 2.53 | Line | 38.54 | * | 56.00 | 46.00 | -17.46 | (QP) |
| 4.81 | Line | 39.25 | * | 56.00 | 46.00 | -16.75 | (QP) |
| 6.79 | Line | 44.18 | * | 60.00 | 50.00 | -15.82 | (QP) |
| 20.39 | Line | 39.46 | * | 60.00 | 50.00 | -20.54 | (QP) |

Remark

- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz; SPA setting in RBW=10KHz,VBW =10KHz, Swp. Time = 0.3 sec./MHz. Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=1MHz,VBW=10Hz, Swp. Time =0.3 sec./MHz.
- (2) All readings are QP Mode value unless otherwise stated AVG in column of 'Note'. If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform. In this case, a " * " marked in AVG Mode column of Interference Voltage Measured.
- (3) Measuring frequency range from 150KHz to 30MHz.




| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 22 °C | Relative Humidity : | 58 % |
| Pressure : | 1014 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 100M-100M | | |

| Freq. (MHz) | Terminal L/N | Measured(dBuV) | | Limits(dBuV) | | Margin (dB) | Note |
|----------------|-----------------|----------------|---------|--------------|---------|----------------|------|
| | | QP-Mode | AV-Mode | QP-Mode | AV-Mode | | |
| 0.39 | Neutral | 41.31 | * | 58.14 | 48.14 | -16.83 | (QP) |
| 1.64 | Neutral | 33.28 | * | 56.00 | 46.00 | -22.72 | (QP) |
| 2.57 | Neutral | 37.34 | * | 56.00 | 46.00 | -18.66 | (QP) |
| 4.14 | Neutral | 41.62 | * | 56.00 | 46.00 | -14.38 | (QP) |
| 6.61 | Neutral | 42.97 | * | 60.00 | 50.00 | -17.03 | (QP) |
| 20.32 | Neutral | 37.28 | * | 60.00 | 50.00 | -22.72 | (QP) |

Remark

- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz; SPA setting in RBW=10KHz,VBW =10KHz, Swp. Time = 0.3 sec./MHz ◦
Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=1MHz,VBW=10Hz, Swp. Time =0.3 sec./MHz ◦
- (2) All readings are QP Mode value unless otherwise stated AVG in column of『Note』. If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform ◦ In this case, a “ * ” marked in AVG Mode column of Interference Voltage Measured ◦
- (3) Measuring frequency range from 150KHz to 30MHz ◦




| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 22 °C | Relative Humidity : | 58 % |
| Pressure : | 1014 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 10M-10M | | |

| Freq. (MHz) | Terminal L/N | Measured(dBuV) | | Limits(dBuV) | | Margin (dB) | Note |
|----------------|-----------------|----------------|---------|--------------|---------|----------------|------|
| | | QP-Mode | AV-Mode | QP-Mode | AV-Mode | | |
| 0.31 | Line | 42.00 | * | 59.89 | 49.89 | -17.89 | (QP) |
| 0.39 | Line | 40.63 | * | 58.04 | 48.04 | -17.41 | (QP) |
| 1.51 | Line | 38.58 | * | 56.00 | 46.00 | -17.42 | (QP) |
| 2.53 | Line | 41.54 | * | 56.00 | 46.00 | -14.46 | (QP) |
| 6.61 | Line | 44.09 | * | 60.00 | 50.00 | -15.91 | (QP) |
| 16.32 | Line | 37.34 | * | 60.00 | 50.00 | -22.66 | (QP) |

Remark

- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz; SPA setting in RBW=10KHz,VBW =10KHz, Swp. Time = 0.3 sec./MHz. Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=1MHz,VBW=10Hz, Swp. Time =0.3 sec./MHz.
- (2) All readings are QP Mode value unless otherwise stated AVG in column of 'Note'. If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform. In this case, a " * " marked in AVG Mode column of Interference Voltage Measured.
- (3) Measuring frequency range from 150KHz to 30MHz.




| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 22 °C | Relative Humidity : | 58 % |
| Pressure : | 1014 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 10M-10M | | |

| Freq. (MHz) | Terminal L/N | Measured(dBuV) | | Limits(dBuV) | | Margin (dB) | Note |
|----------------|-----------------|----------------|---------|--------------|---------|----------------|------|
| | | QP-Mode | AV-Mode | QP-Mode | AV-Mode | | |
| 0.18 | Neutral | 43.97 | * | 64.33 | 54.33 | -20.36 | (QP) |
| 0.39 | Neutral | 41.31 | * | 58.14 | 48.14 | -16.83 | (QP) |
| 2.57 | Neutral | 40.34 | * | 56.00 | 46.00 | -15.66 | (QP) |
| 4.14 | Neutral | 42.62 | * | 56.00 | 46.00 | -13.38 | (QP) |
| 6.61 | Neutral | 42.97 | * | 60.00 | 50.00 | -17.03 | (QP) |
| 18.29 | Neutral | 38.67 | * | 60.00 | 50.00 | -21.33 | (QP) |

Remark

- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz; SPA setting in RBW=10KHz,VBW =10KHz, Swp. Time = 0.3 sec./MHz ◦
Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=1MHz,VBW=10Hz, Swp. Time =0.3 sec./MHz ◦
- (2) All readings are QP Mode value unless otherwise stated AVG in column of『Note』. If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform ◦ In this case, a “ * ” marked in AVG Mode column of Interference Voltage Measured ◦
- (3) Measuring frequency range from 150KHz to 30MHz ◦




| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 22 °C | Relative Humidity : | 58 % |
| Pressure : | 1014 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 100M-100M (ISN) | | |

| Freq. (MHz) | Measured(dBuV) | | Limits(dBuV) | | Safe Margins | |
|----------------|----------------|---------|--------------|---------|--------------|------|
| | QP-Mode | AV-Mode | QP-Mode | AV-Mode | (dBuV) | Note |
| 0.26 | 54.51 | * | 79.45 | 69.45 | -24.94 | (QP) |
| 0.80 | 54.79 | * | 74.00 | 64.00 | -19.21 | (QP) |
| 1.84 | 56.36 | * | 74.00 | 64.00 | -17.64 | (QP) |
| 2.36 | 57.98 | * | 74.00 | 64.00 | -16.02 | (QP) |
| 3.67 | 54.63 | * | 74.00 | 64.00 | -19.37 | (QP) |
| 13.43 | 54.10 | * | 74.00 | 64.00 | -19.90 | (QP) |

Remark

- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz; SPA setting in RBW=10KHz,VBW =10KHz, Swp. Time = 0.3 sec./MHz ◦ Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=1MHz,VBW=10Hz, Swp. Time =0.3 sec./MHz ◦
- (2) All readings are QP Mode value unless otherwise stated AVG in column of『Note』. If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform ◦ In this case, a “ * ” marked in AVG Mode column of Interference Voltage Measured ◦
- (3) Measuring frequency range from 150KHz to 30MHz ◦



4.2 RADIATED EMISSION MEASUREMENT

4.2.1 LIMITS OF RADIATED EMISSION MEASUREMENT (Below 1000MHz)

| FREQUENCY (MHz) | Class A (at 10m) | Class B (at 10m) |
|-----------------|------------------|------------------|
| | dBuV/m | dBuV/m |
| 30 – 230 | 40 | 30 |
| 230 – 1000 | 47 | 37 |

Notes:

- (1) The limit for radiated test was performed according to as following:
CISPR 22/ FCC PART 15B /ICES-003.
- (2) The tighter limit applies at the band edges.
- (3) Emission level (dBuV/m)=20log Emission level (uV/m).

4.2.2 MEASUREMENT INSTRUMENTS LIST

| Item | Kind of Equipment | Manufacturer | Type No. | Serial No. | Calibrated until |
|------|-------------------|-----------------|-----------|------------|------------------|
| 1 | Log-Bicon Antenna | MESS-ELEKTRONIK | VULB 9160 | 3177 | Feb. 06, 2007 |
| 2 | Test Cable | N/A | 10M_OS01 | N/A | Nov. 29, 2006 |
| 3 | Test Cable | N/A | OS01-1/-2 | N/A | Nov. 29, 2006 |
| 4 | Pre-Amplifier | Anritsu | MH648A | M09961 | Nov. 29, 2006 |
| 5 | Spectrum Analyzer | ADVAN TEST | R3261C | 81720298 | Sep. 14, 2006 |
| 6 | Test Receiver | MEB | SMV41 | 130 | Nov. 22, 2006 |
| 7 | Antenna Mast | Chance Most | CMTB-1.5 | N/A | N/A |
| 8 | Turn Table | Chance Most | CMTB-1.5 | N/A | N/A |

Remark: " N/A" denotes No Model No. / Serial No. and No Calibration specified.


4.2.3 TEST PROCEDURE

- The measuring distance of at 10 m shall be used for measurements at frequency up to 1GHz. For frequencies above 1GHz, any suitable measuring distance may be used.
- The EUT was placed on the top of a rotating table 0.8 meters above the ground at a 3m or 10 meter open area test site. The table was rotated 360 degrees to determine the position of the highest radiation.
- The height of the equipment or of the substitution antenna shall be 0.8 m; the height of the test antenna shall vary between 1 m to 4 m. Both horizontal and vertical polarizations of the antenna are set to make the measurement.
- The initial step in collecting conducted emission data is a spectrum analyzer peak detector mode pre-scanning the measurement frequency range. Significant peaks are then marked and then Quasi Peak detector mode re-measured.
- If the Peak Mode measured value compliance with and lower than Quasi Peak Mode Limit, the EUT shall be deemed to meet QP Limits and then no additional QP Mode measurement performed.
- For the actual test configuration, please refer to the related Item –EUT Test Photos.

4.2.4 DEVIATION FROM TEST STANDARD

No deviation

4.2.5 TEST SETUP



4.2.6 EUT OPERATING CONDITIONS

The EUT tested system was configured as the statements of **4.1.6** Unless otherwise a special operating condition is specified in the follows during the testing.


4.2.7 TEST RESULTS

| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 27 °C | Relative Humidity : | 65 % |
| Pressure : | 1017 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 1G-1G | | |

| Freq. (MHz) | Ant. H/V | Reading(RA) (dBuV) | Corr.Factor(CF) (dB) | Measured(FS) (dBuV/m) | Limits(QP) (dBuV/m) | Margin (dB) | Note |
|----------------|-------------|-----------------------|-------------------------|--------------------------|------------------------|----------------|------|
| 33.74 | V | 36.20 | -8.23 | 27.97 | 30.00 | - 2.03 | |
| 112.50 | V | 34.20 | -8.00 | 26.20 | 30.00 | - 3.80 | |
| 125.01 | V | 34.20 | -7.16 | 27.04 | 30.00 | - 2.96 | |
| 250.01 | V | 41.72 | -6.77 | 34.95 | 37.00 | - 2.05 | (QP) |
| 500.04 | V | 33.80 | 0.19 | 33.99 | 37.00 | - 3.01 | |
| 875.10 | V | 26.07 | 6.88 | 32.95 | 37.00 | - 4.05 | (QP) |

Remark :

- (1) Reading in which marked as QP or Peak means measurements by using are Quasi-Peak Mode or Peak Mode with Detector BW=120KHz ; SPA setting in RBW=120KHz, VBW =120KHz, Swp. Time = 0.3 sec./MHz ◦
- (2) All readings are Peak unless otherwise stated QP in column of 『Note』 . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform ◦
- (3) Measuring frequency range from 30MHz to 1000MHz ◦
- (4) If the peak scan value lower limit more than 20dB, then this signal data does not show in table ◦




| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 27 °C | Relative Humidity : | 65 % |
| Pressure : | 1017 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 1G-1G | | |

| Freq. (MHz) | Ant. H/V | Reading(RA) (dBuV) | Corr.Factor(CF) (dB) | Measured(FS) (dBuV/m) | Limits(QP) (dBuV/m) | Margin (dB) | Note |
|----------------|-------------|-----------------------|-------------------------|--------------------------|------------------------|----------------|------|
| 125.01 | H | 30.77 | - 7.16 | 23.61 | 30.00 | - 6.39 | |
| 250.02 | H | 37.85 | - 6.77 | 31.08 | 37.00 | - 5.92 | |
| 375.04 | H | 26.85 | - 2.92 | 23.93 | 37.00 | - 13.07 | |
| 466.69 | H | 27.32 | - 0.59 | 26.73 | 37.00 | - 10.27 | |
| 500.03 | H | 31.12 | 0.19 | 31.31 | 37.00 | - 5.69 | |
| 600.02 | H | 27.42 | 2.55 | 29.97 | 37.00 | - 7.03 | |

Remark :

- (1) Reading in which marked as QP or Peak means measurements by using are Quasi-Peak Mode or Peak Mode with Detector BW=120KHz ; SPA setting in RBW=120KHz, VBW =120KHz, Swp. Time = 0.3 sec./MHz ◦
- (2) All readings are Peak unless otherwise stated QP in column of 『Note』 . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform ◦
- (3) Measuring frequency range from 30MHz to 1000MHz ◦
- (4) If the peak scan value lower limit more than 20dB, then this signal data does not how in table ◦




| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 27 °C | Relative Humidity : | 65 % |
| Pressure : | 1017 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 100M-100M | | |

| Freq. (MHz) | Ant. H/V | Reading(RA) (dBuV) | Corr.Factor(CF) (dB) | Measured(FS) (dBuV/m) | Limits(QP) (dBuV/m) | Margin (dB) | Note |
|----------------|-------------|-----------------------|-------------------------|--------------------------|------------------------|----------------|------|
| 33.25 | V | 36.12 | -8.23 | 27.89 | 30.00 | - 2.11 | |
| 112.42 | V | 34.13 | -8.01 | 26.12 | 30.00 | - 3.88 | |
| 125.02 | V | 33.20 | -7.16 | 26.04 | 30.00 | - 3.96 | |
| 250.02 | V | 41.20 | -6.77 | 34.43 | 37.00 | - 2.57 | (QP) |
| 500.01 | V | 33.40 | 0.19 | 33.59 | 37.00 | - 3.41 | |
| 875.03 | V | 26.11 | 6.88 | 32.99 | 37.00 | - 4.01 | (QP) |

Remark :

- (1) Reading in which marked as QP or Peak means measurements by using are Quasi-Peak Mode or Peak Mode with Detector BW=120KHz ; SPA setting in RBW=120KHz, VBW =120KHz, Swp. Time = 0.3 sec./MHz ◦
- (2) All readings are Peak unless otherwise stated QP in column of 『Note』 . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform ◦
- (3) Measuring frequency range from 30MHz to 1000MHz ◦
- (4) If the peak scan value lower limit more than 20dB, then this signal data does not how in table ◦




| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 27 °C | Relative Humidity : | 65 % |
| Pressure : | 1017 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 100M-100M | | |

| Freq. (MHz) | Ant. H/V | Reading(RA) (dBuV) | Corr.Factor(CF) (dB) | Measured(FS) (dBuV/m) | Limits(QP) (dBuV/m) | Margin (dB) | Note |
|----------------|-------------|-----------------------|-------------------------|--------------------------|------------------------|----------------|------|
| 125.02 | H | 30.15 | - 7.16 | 22.99 | 30.00 | - 7.01 | |
| 250.02 | H | 36.74 | - 6.77 | 29.97 | 37.00 | - 7.03 | |
| 375.00 | H | 26.42 | - 2.92 | 23.50 | 37.00 | - 13.50 | |
| 466.42 | H | 27.11 | - 0.59 | 26.52 | 37.00 | - 10.48 | |
| 500.03 | H | 30.73 | 0.19 | 30.92 | 37.00 | - 6.08 | |
| 600.00 | H | 27.85 | 2.55 | 30.40 | 37.00 | - 6.60 | |

Remark :

- (1) Reading in which marked as QP or Peak means measurements by using are Quasi-Peak Mode or Peak Mode with Detector BW=120KHz ; SPA setting in RBW=120KHz, VBW =120KHz, Swp. Time = 0.3 sec./MHz ◦
- (2) All readings are Peak unless otherwise stated QP in column of 『Note』 . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform ◦
- (3) Measuring frequency range from 30MHz to 1000MHz ◦
- (4) If the peak scan value lower limit more than 20dB, then this signal data does not how in table ◦



5. EMC IMMUNITY TEST

5.1 STANDARD COMPLIANCE/SERVIRITY LEVEL/CRITERIA

| Tests Standard No. | TEST SPECIFICATION Level | Test Mode Test Ports | Perform. Criteria | Remark |
|---|---|---------------------------------|----------------------|--------|
| 1. ESD IEC/EN 61000-4-2 | 8KV air discharge 4KV contact discharge | Direct Mode | B | |
| | 4KV HCP discharge 4KV VCP discharge | Indirect Mode | B | |
| 2. RS IEC/EN 61000-4-3 | 80 MHz to 1000 MHz 3V/m(rms), 1 KHz, 80%, AM modulated | Enclosure | A | |
| 3. EFT/Burst IEC/EN 61000-4-4 | 1.0KV(peak) 5/50ns Tr/Th 5KHz Repetition Freq. | Power Supply Port | B | |
| | 0.5 KV(peak) 5/50ns Tr/Th 5KHz Repetition Freq. | CTL/Signal Data Line Port | B | |
| 4. Surges IEC/EN 61000-4-5 | 1 KV(5P/5N) 1.2/50(8/20) Tr/Th us | L-N | B | |
| | 2 KV(5P/5N) 1.2/50(8/20) Tr/Th us | L-PE N-PE | B | |
| 5 Injected Current IEC/EN 61000-4-6 | 0.15 MHz to 80 MHz 3V(rms), 1KHz 80%, AM Modulated 150Ω source impedance | CTL/Signal Port | A | |
| | 0.15 MHz to 80 MHz 3V(rms), 1KHz 80%, AM Modulated 150Ω source impedance | AC Power Port | A | |
| | 0.15 MHz to 80 MHz 3V(rms), 1KHz 80%, AM Modulated 150Ω source impedance | DC Power Port | A | N/A |
| 6. Power Frequency Magnetic Field IEC/EN 61000-4-8 | 50 Hz, 1A/m | Enclosure | A | |
| 7. Volt. Interruptions Volt. Dips IEC/EN 61000-4-11 | Voltage dip > 95% | | B | |
| | Voltage dip 30% | AC Power Port | C | |
| | Interruption > 95% | | C | |

* Remark:

N/A : denotes test is not applicable in this Test Report

(1) : The EUT is a battery operating device and no any other cable connection to PC device.

(2) : Applicable only to cables which according to the manufacturer's specification supports communication on cables lengths greater than 3 m.

(3) : Applicable only to equipment containing devices susceptible to magnetic fields

5.2 GENERAL PERFORMANCE CRITERIA

According to **EN55024** standard, the general performance criteria as following:

| | |
|--------------------|--|
| Criterion A | <p>The equipment shall continue to operate as intended without operator intervention. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer when the equipment is used as intended. The performance level may be replaced by a permissible loss of performance.</p> <p>If the minimum performance level or the permissible performance loss is not specified by the manufacturer, then either of these may be derived from the product description and documentation, and by what the user product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.</p> |
| Criterion B | <p>After the test, the equipment shall continue to operate as intended without operator intervention. No degradation of performance or loss of function is allowed, after the application of the phenomenon below a performance level specified by the manufacturer, when the equipment is used as intended. The performance level may be replaced by a permissible loss of performance.</p> <p>During the test, degradation of performance is allowed. However, no change of operating state if stored data allowed to persist after the test. If the minimum performance level (or the permissible performance loss) is not specified by the manufacturer, then either of these may be derived from the product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.</p> |
| Criterion C | <p>Loss of function is allowed, provided the function is self-recoverable, or can be restored by the operation of the controls by the user in accordance with the manufacturer's instructions.</p> <p>Functions, and/or information stored in non-volatile memory, or protected by a battery backup, shall not be lost.</p> |

5.3 GENERAL PERFORMANCE CRITERIA TEST SETUP

The EUT tested system was configured as the statements of **4.1.6** Unless otherwise a special operating condition is specified in the follows during the testing.

5.4 ESD TESTING

5.4.1 TEST SPECIFICATION

| | |
|----------------------|---|
| Basic Standard: | IEC/EN 61000-4-2 |
| Discharge Impedance: | 330 ohm / 150 pF |
| Required Performance | B |
| Discharge Voltage: | Air Discharge : 2kV/4kV/8kV (Direct) Contact Discharge : 2kV/4kV (Direct/Indirect) |
| Polarity: | Positive & Negative |
| Number of Discharge: | Air Discharge: min. 20 times at each test point Contact Discharge: min. 200 times in total |
| Discharge Mode: | Single Discharge |
| Discharge Period: | 1 second minimum |

5.4.2 MEASUREMENT INSTRUMENTS

| Item | Kind of Equipment | Manufacturer | Type No. | Serial No. | Calibrated until |
|------|-------------------|--------------|----------|------------|------------------|
| 1 | ESD Simulator | Thermo | MZ-15/EC | 0502184 | Nov. 27, 2006 |

Remark: " N/A" denotes No Model No. / Serial No. and No Calibration specified.

5.4.3 TEST PROCEDURE


The test generator necessary to perform direct and indirect application of discharges to the EUT in the following manner:

- a. Contact discharge was applied to conductive surfaces and coupling planes of the EUT.
During the test, it was performed with single discharges. For the single discharge time between successive single discharges was at least 1 second. The EUT shall be exposed to at least 200 discharges, 100 each at negative and positive polarity, at a minimum of four test points. One of the test points shall be subjected to at least 50 indirect discharges to the center of the front edge of the horizontal coupling plane. The remaining three test points shall each receive at least 50 direct contact discharges.
If no direct contact test points are available, then at least 200 indirect discharges shall be applied in the indirect mode. Test shall be performed at a maximum repetition rate of one discharge per second.
Vertical Coupling Plane (VCP):
The coupling plane, of dimensions 0.5m x 0.5m, is placed parallel to, and positioned at a distance 0.1m from, the EUT, with the Discharge Electrode touching the coupling plane.
The four faces of the EUT will be performed with electrostatic discharge.
Horizontal Coupling Plane (HCP):
The coupling plane is placed under to the EUT. The generator shall be positioned vertically at a distance of 0.1m from the EUT, with the Discharge Electrode touching the coupling plane.
The four faces of the EUT will be performed with electrostatic discharge.
- b. Air discharges at insulation surfaces of the EUT.
It was at least ten single discharges with positive and negative at the same selected point.
- c. For the actual test configuration, please refer to the related Item –EUT Test Photos.

5.4.4 DEVIATION FROM TEST STANDARD

No deviation

5.4.5 TEST SETUP



Note:

TABLE-TOP EQUIPMENT

The configuration consisted of a wooden table 0.8 meters high standing on the Ground Reference Plane. The GRP consisted of a sheet of aluminum at least 0.25mm thick, and 2.5 meters square connected to the protective grounding system. A Horizontal Coupling Plane (1.6m x 0.8m) was placed on the table and attached to the GRP by means of a cable with 940k total impedance. The equipment under test, was installed in a representative system as described in section 7 of IEC /EN 61000-4-2, and its cables were placed on the HCP and isolated by an insulating support of 0.5mm thickness. A distance of 1-meter minimum was provided between the EUT and the walls of the laboratory and any other metallic structure.

FLOOR-STANDING EQUIPMENT

The equipment under test was installed in a representative system as described in section 7 of IEC/EN 61000-4-2, and its cables were isolated from the Ground Reference Plane by an insulating support of 0.1-meter thickness. The GRP consisted of a sheet of aluminum that is at least 0.25mm thick, and 2.5meters square connected to the protective grounding system and extended at least 0.5 meters from the EUT on all sides.

5.4.6 TEST RESULTS

| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 22 °C | Relative Humidity : | 58 % |
| Pressure : | 1007.9 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 1G-1G | | |

| Mode | Air Discharge | | | | | | | | Contact Discharge | | | | | | | |
|----------|---------------|---|-----|---|-----|---|------|---|-------------------|---|-----|---|-----|---|-----|---|
| | 2KV | | 4KV | | 8KV | | 12KV | | 2KV | | 4KV | | 6KV | | 8KV | |
| Location | P | N | P | N | P | N | P | N | P | N | P | N | P | N | P | N |
| 1 | | | | | | | | | A | A | A | A | | | | |
| 2 | | | | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | |
| Criteria | B | | | | | | | | B | | | | | | | |
| Result | N/A | | | | | | | | A | | | | | | | |
| Judgment | N/A | | | | | | | | PASS | | | | | | | |


| Mode | HCP Discharge | | | | | | | | VCP Discharge | | | | | | | |
|----------|---------------|---|-----|---|-----|---|-----|---|---------------|---|-----|---|-----|---|-----|---|
| | 2KV | | 4KV | | 6KV | | 8KV | | 2KV | | 4KV | | 6KV | | 8KV | |
| Location | P | N | P | N | P | N | P | N | P | N | P | N | P | N | P | N |
| 1 | A | A | A | A | | | | | A | A | A | A | | | | |
| 2 | A | A | A | A | | | | | A | A | A | A | | | | |
| 3 | A | A | A | A | | | | | A | A | A | A | | | | |
| 4 | A | A | A | A | | | | | A | A | A | A | | | | |
| Criteria | B | | | | | | | | B | | | | | | | |
| Result | A | | | | | | | | A | | | | | | | |
| Judgment | PASS | | | | | | | | PASS | | | | | | | |

Note:

- 1) P/N denotes the Positive/Negative polarity of the output voltage.
- 2) Test condition:
Direct / Indirect (HCP/VCP) discharges: Minimum 50 times (Positive/Negative) at each point. Air discharges: Minimum 10 times (Positive/Negative) at each point.
- 3) Test location(s) in which discharge (Air and contact discharge) to be applied illustrated by photos shown in next page(s)
- 4) The Indirect (HCP/VCP) discharges description of test point as following:
1.left side 2.right side 3.front side 4.rear side
- 5) N/A - denotes test is not applicable in this test report
- 6) Criteria A: There was no change operated with initial operating during the test.
- 7) Criteria B: The EUT function loss during the test, but self-recoverable after the test.

8) Criteria C: The system shut down during the test.

5.4.7 PHOTO(S) SHOWN THE LOCATION(S) OF ESD EVALUATED



5.5 RS TESTING

5.5.1 TEST SPECIFICATION

| | |
|----------------------|------------------------------------|
| Basic Standard: | IEC/EN 61000-4-3 |
| Required Performance | A |
| Frequency Range: | 80 MHz - 1000 MHz |
| Field Strength: | 3 V/m |
| Modulation: | 1kHz Sine Wave, 80%, AM Modulation |
| Frequency Step: | 1 % of fundamental |
| Polarity of Antenna: | Horizontal and Vertical |
| Test Distance: | 3 m |
| Antenna Height: | 1.5 m |
| Dwell Time: | at least 3 seconds |

5.5.2 MEASUREMENT INSTRUMENTS

| Item | Kind of Equipment | Manufacturer | Type No. | Serial No. | Calibrated until |
|------|---------------------|-----------------|-----------------|------------|------------------|
| 1 | Signal Generator | R&S | SMT 06 | 832080/007 | Aug. 03, 2006 |
| 2 | Power Amplifier(RS) | M2S | AC8113-800/250A | 9904-113 | Apr. 09, 2008 |
| 3 | Antenna(500W) | MESS-ELEKTRONIK | VULB9161 | 4022 | Aug. 16, 2006 |

Remark: " N/A" denotes No Model No. / Serial No. and No Calibration specified.

5.5.3 TEST PROCEDURE

The EUT and support equipment, which are placed on a table that is 0.8 meter above ground and the testing was performed in a fully-anechoic chamber.

The testing distance from antenna to the EUT was 3 meters.


The other condition as following manner:

- The field strength level was 3V/m.
- The frequency range is swept from 80 MHz to 1000 MHz, with the signal 80%amplitude modulated with a 1kHz sine wave. The rate of sweep did not exceed 1.5×10^{-3} decade/s. Where the frequency range is swept incrementally, the step size was 1% of fundamental.
- Sweep Frequency 900 MHz, with the Duty Cycle:1/8 and Modulation: Pulse 217 Hz(if applicable)
- The dwell time at each frequency shall be not less than the time necessary for the EUT to be able to respond.
- The test was performed with the EUT exposed to both vertically and horizontally polarized fields on each of the four sides.
- For the actual test configuration, please refer to the related Item –EUT Test Photos.

5.5.4 DEVIATION FROM TEST STANDARD

No deviation

5.5.5 TEST SETUP



Note:

TABLE-TOP EQUIPMENT

The EUT installed in a representative system as described in section 7 of IEC/EN 61000-4-3 was placed on a non-conductive table 0.8 meters in height. The system under test was connected to the power and signal wire according to relevant installation instructions.

FLOOR-STANDING EQUIPMENT

The EUT installed in a representative system as described in section 7 of IEC/EN 61000-4-3 was placed on a non-conductive wood support 0.1 meters in height. The system under test was connected to the power and signal wire according to relevant installation instructions.

5.5.6 TEST RESULTS

| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 22 °C | Relative Humidity : | 58 % |
| Pressure : | 1007.9 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 1G-1G | | |

| Frequency Range (MHz) | RF Field Position | R.F. Field Strength | Azimuth | Perform. Criteria | Results | Judgment |
|--------------------------|----------------------|--|---------|----------------------|----------|-------------|
| 80MHz - 1000MHz | H / V | 3 V/m (rms) AM Modulated 1000Hz, 80% | 0 | A | A | PASS |
| | | | 90 | | | |
| | | | 180 | | | |
| | | | 270 | | | |

Note:

- 1) P/N denotes the Positive/Negative polarity of the output voltage.
- 2) N/A - denotes test is not applicable in this test report.
- 3) Criteria A: There was no change operated with initial operating during the test.
- 4) Criteria B: The EUT function loss during the test, but self-recoverable after the test.
- 5) Criteria C: The system shut down during the test.

5.6 EFT/BURST TESTING

5.6.1 TEST SPECIFICATION

| | |
|----------------------|---|
| Basic Standard: | IEC/EN 61000-4-4 |
| Required Performance | B |
| Test Voltage: | Power Line : 1 kV Signal/Control Line : 0.5 KV |
| Polarity: | Positive & Negative |
| Impulse Frequency: | 5 kHz |
| Impulse Wave shape : | 5/50 ns |
| Burst Duration: | 15 ms |
| Burst Period: | 300 ms |
| Test Duration: | Not less than 1 min. |

5.6.2 MEASUREMENT INSTRUMENTS

| Item | Kind of Equipment | Manufacturer | Type No. | Serial No. | Calibrated until |
|------|--------------------------|--------------|-------------|------------|------------------|
| 1 | EMC Immunity Test System | Thermo | EMCPRO PLUS | 0502176 | Dec. 01, 2006 |
| 2 | Capacitive Clamp | Thermo | CCL | 0502218 | N/A |

Remark: " N/A" denotes No Model No. / Serial No. and No Calibration specified.

5.6.3 TEST PROCEDURE

The EUT and support equipment, are placed on a table that is 0.8 meter above a metal ground plane measured 1m*1m min. and 0.65mm thick min.


The other condition as following manner:

- The length of power cord between the coupling device and the EUT should not exceed 1 meter.
- Both positive and negative polarity discharges were applied.
- The duration time of each test sequential was 1 minute
- For the actual test configuration, please refer to the related Item –EUT Test Photos.

5.6.4 DEVIATION FROM TEST STANDARD

No deviation

5.6.5 TEST SETUP



Note:

TABLE-TOP EQUIPMENT

The configuration consisted of a wooden table (0.8m high) standing on the Ground Reference Plane. The GRP consisted of a sheet of aluminum (at least 0.25mm thick and 2.5m square) connected to the protective grounding system. A minimum distance of 0.5m was provided between the EUT and the walls of the laboratory or any other metallic structure.

FLOOR-STANDING EQUIPMENT

The EUT installed in a representative system as described in section 7 of IEC/EN 61000-4-4 and its cables, were isolated from the Ground Reference Plane by an insulating support that is 0.1-meter thick. The GRP consisted of a sheet of aluminum (at least 0.25mm thick and 2.5m square) connected to the protective grounding system.

5.6.6 TEST RESULTS

| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 22 °C | Relative Humidity : | 58 % |
| Pressure : | 1007.9 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 1G-1G | | |

| Mode | (X) AC Power Line | | () DC Power Line | | (X) Signal/Control Line | |
|------------------------|---------------------|---------|-------------------|---------|---------------------------|---------|
| Test Level | 1KV | | 0.5KV | | 0.5KV | |
| Port(s) | Polarity | Results | Polarity | Results | Polarity | Results |
| Line (L) | P | A | P | | P | |
| | N | A | N | | N | |
| Neutral (N) | P | A | P | | P | |
| | N | A | N | | N | |
| Ground (PE) | P | A | P | | P | |
| | N | A | N | | N | |
| Signal/Control Line | P | | P | | P | A |
| | N | | N | | N | A |
| Criteria | B | | B | | B | |
| Result | A | | N/A | | A | |
| Judgment | PASS | | N/A | | PASS | |

Note:

- 1) P/N denotes the Positive/Negative polarity of the output voltage.
- 2) N/A - denotes test is not applicable in this test report
- 3) Criteria A: There was no change operated with initial operating during the test.
- 4) Criteria B: The EUT function loss during the test, but self-recoverable after the test.
- 5) Criteria C: The system shut down during the test.

5.7 SURGE TESTING

5.7.1 TEST SPECIFICATION

| | |
|------------------------|--|
| Basic Standard: | IEC/EN 61000-4-5 |
| Required Performance | B |
| Wave-Shape: | Combination Wave 1.2/50 us Open Circuit Voltage 8 /20 us Short Circuit Current |
| Test Voltage: | Power Line : 0.5 kV, 1 kV, 2 kV |
| Surge Input/Output: | L1-L2, L1-PE, L2-PE |
| Generator Source: | 2 ohm between networks |
| Impedance: | 12 ohm between network and ground |
| Polarity: | Positive/Negative |
| Phase Angle: | 0 /90/180/270 |
| Pulse Repetition Rate: | 1 time / min. (maximum) |
| Number of Tests: | 5 positive and 5 negative at selected points |

5.7.2 MEASUREMENT INSTRUMENTS

| Item | Kind of Equipment | Manufacturer | Type No. | Serial No. | Calibrated until |
|------|--------------------------|--------------|-------------|------------|------------------|
| 1 | EMC Immunity Test System | Thermo | EMCPRO PLUS | 0502176 | Dec. 01, 2006 |

Remark: " N/A" denotes No Model No. / Serial No. and No Calibration specified.

5.7.3 TEST PROCEDURE

a. For EUT power supply:

The surge is to be applied to the EUT power supply terminals via the capacitive coupling network. Decoupling networks are required in order to avoid possible adverse effects on equipment not under test that may be powered by the same lines, and to provide sufficient decoupling impedance to the surge wave. The power cord between the EUT and the coupling/decoupling networks shall be 2meters in length (or shorter).

b. For test applied to unshielded unsymmetrically operated interconnection lines of EUT:

The surge is applied to the lines via the capacitive coupling. The coupling /decoupling networks shall not influence the specified functional conditions of the EUT. The interconnection line between the EUT and the coupling/decoupling networks shall be 2 meters in length (or shorter).

c. For test applied to unshielded symmetrically operated interconnection /telecommunication lines of EUT:


The surge is applied to the lines via gas arrestors coupling. Test levels below the ignition point of the coupling arrestor cannot be specified. The interconnection line between the EUT and the coupling/decoupling networks shall be 2 meters in length (or shorter).

d. For the actual test configuration, please refer to the related Item –EUT Test Photos.

5.7.4 DEVIATION FROM TEST STANDARD

No deviation

5.7.5 TEST SETUP



5.7.6 TEST RESULTS

| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 22 °C | Relative Humidity : | 58 % |
| Pressure : | 1007.9 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 1G-1G | | |

| Wave Form EUT Ports Tested | 1.2/50(8/20)Ti/Th us | | | | | | Criteria | Judgment |
|-------------------------------|----------------------|-------|---------|-------|-----|---|----------|----------|
| | Polarity | Phase | Voltage | | | | | |
| 0.5kV | | | 1kV | 1.5kV | 2kV | | | |
| L - N | +/- | 0° | A | A | | | B | PASS |
| | +/- | 90° | A | A | | | | |
| | +/- | 180° | A | A | | | | |
| | +/- | 270° | A | A | | | | |
| L - PE | +/- | 0° | A | A | A | A | B | PASS |
| | +/- | 90° | A | A | A | A | | |
| | +/- | 180° | A | A | A | A | | |
| | +/- | 270° | A | A | A | A | | |
| N - PE | +/- | 0° | A | A | A | A | B | PASS |
| | +/- | 90° | A | A | A | A | | |
| | +/- | 180° | A | A | A | A | | |
| | +/- | 270° | A | A | A | A | | |
| Signal Line (N/A) | +/- | 0° | | | | | B | N/A |
| | +/- | 90° | | | | | | |
| | +/- | 180° | | | | | | |
| | +/- | 270° | | | | | | |

Note:

- 1) Polarity and Numbers of Impulses : 5 Pst / Ngst at each tested mode
- 2) N/A - denotes test is not applicable in this Test Report
- 3) Criteria A: There was no change operated with initial operating during the test.
- 4) Criteria B: The EUT function loss during the test, but self-recoverable after the test.
- 5) Criteria C: The system shut down during the test.

5.8 INJECTION CURRENT TESTING

5.8.1 TEST SPECIFICATION

| | |
|----------------------|------------------------------------|
| Basic Standard: | IEC/EN 61000-4-6 |
| Required Performance | A |
| Frequency Range: | 0.15 MHz - 80 MHz |
| Field Strength: | 3 Vr.m.s. |
| Modulation: | 1kHz Sine Wave, 80%, AM Modulation |
| Frequency Step: | 1 % of fundamental |
| Dwell Time: | at least 3 seconds |

5.8.2 MEASUREMENT INSTRUMENTS

| Item | Kind of Equipment | Manufacturer | Type No. | Serial No. | Calibrated until |
|------|---------------------|--------------|-----------|------------|------------------|
| 1 | Signal Generator | IFR | 2023A | 202301/368 | Mar. 24, 2007 |
| 2 | Power Amplifier(CS) | M2S | A0122-250 | 9902-111 | Mar. 27, 2007 |
| 3 | CDN | MEB | M3 | 13389 | Jun. 06, 2007 |
| 4 | EM Clamp | MEB | KEMZ 801 | 14291 | Jul. 07, 2007 |

Remark: " N/A" denotes No Model No. / Serial No. and No Calibration specified.

5.8.3 TEST PROCEDURE

The EUT and support equipment, are placed on a table that is 0.8 meter above a metal ground plane measured 1m*1m min. and 0.65mm thick min.


The other condition as following manner:

- The field strength level was 3V.
- The frequency range is swept from 150 KHz to 80 MHz, with the signal 80%amplitude modulated with a 1kHz sine wave. The rate of sweep did not exceed 1.5×10^{-3} decade/s. Where the frequency range is swept incrementally, the step size was 1% of fundamental.
- The dwell time at each frequency shall be not less than the time necessary for the EUT to be able to respond.
- For the actual test configuration, please refer to the related Item –EUT Test Photos.

5.8.4 DEVIATION FROM TEST STANDARD

No deviation

5.8.5 TEST SETUP



For the actual test configuration, please refer to the related Item –EUT Test Photos.

NOTE:

FLOOR-STANDING EQUIPMENT

The equipment to be tested is placed on an insulating support of 0.1 meters height above a ground reference plane. All relevant cables shall be provided with the appropriate coupling and decoupling devices at a distance between 0.1 meters and 0.3 meters from the projected geometry of the EUT on the ground reference plane.

5.8.6 TEST RESULTS

| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 22 °C | Relative Humidity : | 58 % |
| Pressure : | 1007.9 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 1G-1G | | |

| Test Ports (Mode) | Freq. Range MHz) | Field Strength | Perform. Criteria | Results | Judgment |
|---------------------------------|---------------------|--|----------------------|------------|-------------|
| Input/ Output AC. Power Port | 0.15 ---80 | 3V(rms) AM Modulated 1000Hz, 80% | A | A | PASS |
| Input/ Output DC. Power Port | 0.15 --- 80 | | A | N/A | N/A |
| Signal Line (RJ-45) | 0.15 --- 80 | | A | A | PASS |

Note:

- 1) N/A - denotes test is not applicable in this Test Report.
- 2) Criteria A: There was no change operated with initial operating during the test.
- 3) Criteria B: The EUT function loss during the test, but self-recoverable after the test.
- 4) Criteria C: The system shut down during the test.

5.9 POWER FREQUENCY MAGNETIC FIELD TESTING

5.9.1 TEST SPECIFICATION

| | |
|----------------------|-------------------------|
| Basic Standard: | IEC/EN 61000-4-8 |
| Required Performance | A |
| Frequency Range: | 50Hz |
| Field Strength: | 1 A/m |
| Observation Time: | 1 minute |
| Inductance Coil: | Rectangular type, 1mx1m |

5.9.2 MEASUREMENT INSTRUMENTS

| Item | Kind of Equipment | Manufacturer | Type No. | Serial No. | Calibrated until |
|------|-------------------------------|--------------|------------------|------------|------------------|
| 1 | Magnetic Field Test Generator | FCC | F-100-4-8-G-125A | 04029 | Apr. 06, 2007 |

Remark: " N/A" denotes No Model No. / Serial No. and No Calibration specified.

5.9.3 TEST PROCEDURE

The EUT and support equipment, are placed on a table that is 0.8 meter above a metal ground plane measured 1m*1m min. and 0.65mm thick min.


The other condition as following manner:

- The equipment cabinets shall be connected to the safety earth directly on the GRP via the earth terminal of the EUT.
- The cables supplied or recommended by the equipment manufacturer shall be used. 1 meter of all cables used shall be exposed to the magnetic field.
- For the actual test configuration, please refer to the related Item –EUT Test Photos.

5.9.4 DEVIATION FROM TEST STANDARD

No deviation

5.9.5 TEST SETUP



Note:

TABLE-TOP EQUIPMENT

The equipment shall be subjected to the test magnetic field by using the induction coil of standard dimension (1 m x 1 m). The induction coil shall then be rotated by 90 degrees in order to expose the EUT to the test field with different orientations.

FLOOR-STANDING EQUIPMENT

The equipment shall be subjected to the test magnetic field by using induction coils of suitable dimensions. The test shall be repeated by moving and shifting the induction coils, in order to test the whole volume of the EUT for each orthogonal direction. The test shall be repeated with the coil shifted to different positions along the side of the EUT, in steps corresponding to 50 % of the shortest side of the coil. The induction coil shall then be rotated by 90 degrees in order to expose the EUT to the test field with different orientations.

5.9.6 TEST RESULTS

| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 22 °C | Relative Humidity : | 58 % |
| Pressure : | 1007.9 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 1G-1G | | |

| Test Mode | Test Level | Antenna aspect | Duration (s) | Perform Criteria | Results | Judgment |
|-----------|------------|----------------|--------------|------------------|---------|----------|
| Enclosure | 1 A/m | X | 60 s | A | A | PASS |
| Enclosure | 1 A/m | Y | 60 s | A | A | PASS |
| Enclosure | 1 A/m | Z | 60 s | A | A | PASS |

Note:

- 1) N/A - denotes test is not applicable in this test report
- 2) Criteria A: There was no change operated with initial operating during the test.
- 3) Criteria B: The EUT function loss during the test, but self-recoverable after the test.
- 4) Criteria C: The system shut down during the test.

5.10 VOLTAGE INTERRUPTION/DIPS TESTING

5.10.1 TEST SPECIFICATION

| | |
|-------------------------|---|
| Basic Standard: | IEC/EN 61000-4-11 |
| Required Performance | B (For >95% Voltage Dips) C (For 30% Voltage Dips) C (For >95% Voltage Interruptions) |
| Test Duration Time: | Minimum three test events in sequence |
| Interval between Event: | Minimum ten seconds |
| Phase Angle: | 0°/45°/90°/135°/180°/225°/270°/315°/360° |
| Test Cycle: | 3 times |

5.10.2 MEASUREMENT INSTRUMENTS

| Item | Kind of Equipment | Manufacturer | Type No. | Serial No. | Calibrated until |
|------|--------------------------|--------------|-------------|------------|------------------|
| 1 | EMC Immunity Test System | Thermo | EMCPRO PLUS | 0502176 | Dec. 01, 2006 |

Remark: " N/A" denotes No Model No. / Serial No. and No Calibration specified.


5.10.3 TEST PROCEDURE

The EUT shall be tested for each selected combination of test levels and duration with a sequence of three dips/interruptions with intervals of 10 s minimum (between each test event). Each representative mode of operation shall be tested. Abrupt changes in supply voltage shall occur at zero crossings of the voltage waveform.

5.10.4 DEVIATION FROM TEST STANDARD

No deviation

5.10.5 TEST SETUP



For the actual test configuration, please refer to the related Item –EUT Test Photos.

5.10.6 TEST RESULTS

| | | | |
|---------------|--|---------------------|--------------|
| EUT : | 32-Bit PCI Bus 10/100/1000Mbps Ethernet Card | Model No. : | DGE-528T |
| Temperature : | 24 °C | Relative Humidity : | 58 % |
| Pressure : | 1014.5 hPa | Test Power : | AC 230V/50Hz |
| Test Mode : | 1G-1G | | |

| Voltage Reduction | Periods | Perform Criteria | Results | Judgment |
|----------------------|---------|---------------------|----------|-------------|
| Voltage dip > 95% | 0.5 | B | A | PASS |
| Voltage dip 30% | 25 | C | A | PASS |
| Interruption > 95% | 250 | C | C | PASS |

Note:

- 1). N/A - denotes test is not applicable in this test report.
- 2) Criteria A: There was no change operated with initial operating during the test.
- 3) Criteria B: The EUT function loss during the test, but self-recoverable after the test.
- 4) Criteria C: The system shut down during the test.

6. EUT TEST PHOTO

Conducted Measurement Photos



Radiated Measurement Photos

